Pimpri Chinchwad Municipal Corporation

Date:- 7/8/2018

Supplying & Fixing Cobbels stone of 65mm thick with natural finish

Rate as per SSR-2017-18

Supplying & Fixing Cobbels stone of size 100mm x 100mm x 65mm thick of black color with natural finish & four side machine cut Granite Cobells of different colours & fixing in 1:6 cement morter on an average 55mm thick cement bed. Gaps in two stones to be filled by 1:3 cement morter & filler of colour cement with sunk pointing and machine cut straight line looks square shape as per detail drawing & specifications & as per the directed by engineer-in-charge including transportation, Loading, unloading and all other taxes and excluding GST.

Quantity for 1 sqm

Sr.No	Description	Unit	Quantity	Rate	Amount	Item
1	**Labour**					
i	Mason IInd Class Skilled	Day	0.15	494	74.1	
ii	Mazdoor (M)	Day	0.10	448	44.8	
iii	Mazdoor - Unskilled Heavy Female	Day	0.10	448	44.8	
iv	Mazdoor - Unskilled Heavy Female for Rubbing & Polishing	Day	0.10	448	44.8	
v	Bhisti (Mixing / Curing) - Semi Skilled	Day	0.025	467	11.7	
	Total Cost of Labour				**220.2**	
2	**Material**					
i	Cement	M.T	0.0145	4200	60.9	
ii	Artificial sand	Cu.m	0.02	517	10.34	
iii	Granite Cobble 100x100x65mm (Black Color)	No	100.00	14	1400	
	Total Cost of Material				**1471.24**	
	Total 1+2				**1691.42**	
3	**Total**		1691.42	0.5%	8.46	
	Sunderies @ 1/2%				**1699.9**	
4	**Total**					
	Water charges @ 1%		1699.9	1.00%	17.00	
	Total				**1716.87**	
5	Over head charges 10%		1400.0	10.00%	**140.00**	
				Total Rate for 1 sqm	**1856.87**	**Per Sq.m**
Rate is Proposed for Supplying & Fixing Cobbels stone of size 100x 100x65mm thick with natural finish Rs.					**1856.87**	**Per Sq.m**
Rate In Words :- Rs.One thousand Eight Hundred Fifty Six and Eighty Seven Paise only						

PaveTech Consultants
Pune

Junior Engineer
PCMC

Deputy Engineer
PCMC

Executive Engineer
PCMC

Rate is Approved for Supplying & Fixing Cobbels stone of size 100x 100x65mm thick with natural finish Rs.	**1856.87**	**Per Sq.m**
Rate In Words :- Rs.One thousand Eight Hundred Fifty Six and Eighty Seven Paise only		

Joint City Engineer
PCMC