Pimpri Chinchwad Municipal Corporation

Name of the Work: Providing and supplying with fixing the FRP dust bin of 42 lit. capacity

Rate analysis

Date:- 7/8/18

Item: Providing and supplying with fixing the FRP dust bin of 42 lit. capacity , Outer cover of FRP Finish (600mm dia X 1325mm height) to be fixed 1125mm height above footpath finish level having dumping opening of size (500mm (W) x 100MM (H)) & openable door on the rear side of 600mm width, consisting of removable internal bucket of FRP Finish (500mm dia X 1000mm height) anchored internally on two side, as per drawings and designs, specifications etc complete as directed by Engineer-in-charge. including transportation, loading, unloading and including all other taxes and excluding GST.

Lowest rate from comparative, hence rate proposed is Rate is Approved as Rs.5400 (Five Thousand and Four Hundred Rs. only) Per No.

Jr. Engineer (BRTS)
PCMC, Pimpri-18

Dy. Engineer (BRTS)
PCMC, Pimpri-18

Executive. Engineer (BRTS)
PCMC, Pimpri-18

Rate is Approved as Rs.5400 (Five Thousand and Four Hundred Rs. only) Per No.

Jt. City Engineer (BRTS)
PCMC, Pimpri-18

Section

Plan

Note :- Material & Size to be as per specification.

Smart City : Area Based Development Aundh - Baner - Balewadi Pilot Pune Smart City Development Corporation Ltd.	S3 - MAHDJI SHINDE ROAD , AUNDH : Westend to Bridge Rev. No. / Date / Revised By / Description	Consulting Team PAVETECH CONSULTANTS Project Management Consultant T R I PRASANNA DESAI Architecture Interior & Urban Design Consultants	TENDER DRAWING (DRAFT COPY) Dealt by : Anikita Anand Date 19-01-2018 Litter Bin Fixing Detail	Job No. 199	D 38