Pimpri Chinchwad Municipal Corporation

Name of the Work: Providing and applying Exposed aggregate systems.

Rate analysis

Date:- 7/8/2018

Item: Providing and applying Exposed aggregate systems mixing 8 to 10mm pebbles in green, white and yellow colour with the similar ratio of 14kg per Sq.m, placing of 6-inch M-20 grade of concrete floating the surface and finishing expose aggregate system. After curing applying Acrylic Sealer on pebbles etc complete. including transportation, loading, unloading and including all other taxes and excluding GST.

Lowest rate from comparative, hence rate proposed is 1250.00 (Rs. One Thousand Two Hundred Fifty Only) Per Sq.m.

Jr. Engineer (BRTS)	Dy. Engineer (BRTS)	Executive. Engineer (BRTS)
PCMC, Pimpri-18	PCMC, Pimpri-18	PCMC, Pimpri-18

Rate is Approved asisRs. 1250.00(Rs. One Thousand Two Hundred Fifty Only) Per Sq.m.

Jt. City Engineer (BRTS)

PCMC, Pimpri-18

SECTION XX (SCALE 1:10)

DETAIL YY (Scale 1:5)

TENDER DRAWING (DRAFT COPY)

PCMC Street Development Akurdi - Pimple Nilakh Pilot Pimpri Chinchwad Municipal Corporation	S1 - Pimple Nilakh , S2, S3, S4, and S5 - Akurdi			Consulting Team PAVETECH CONSULTANTS Project Management Consultants PRASANNA DESAI Architects & Urban Design Consultants	Drawn by : Ankita Anand Date : 17/01/2018 Concrete Bollard Detail Job No: 200 202 D 10 10 53
	Rev. No.	Date	Revised By	Description	
	00	00			
	00	00			