Pimpri Chinchwad Municipal Corporation

Name of the Work: Providing and Fixing Sagar Black Sand Stone Seat out. Date:- 7/8/18

Rate Analysis

Item: Providing and Fixing Sagar black sandstone **bench of Type D-73, [(01 Top Slab - (3'5" x 1'4" x 3") and 02 Supports - (6" x 1'1" x 1'10")]** with top surface polished and remaining surfaces natural finish, fixed with cladex chemical as per Detailed Drawing Attached and Type suggested by Architect and as directed by Engineer In charge including transportation, loading, unloading and all other taxes and excluding GST.

Lowest rate from comparative, hence rate proposed is Rs. 16000 (Rs. Sixteen Thousand only) Per No for D-73 Type [Top Slab - (3'5" x 1'4" x 3"), Supports - (6" x 1'1" x 1'10")].

Jr. Engineer (BRTS)	By. Engineer (BRTS)	Executive. Engineer (BRTS)
PCMC, Pimpri-18	PCMC, Pimpri-18	PCMC, Pimpri-18

Rate is Approved as Rs. 16000 (Rs. Sixteen Thousand Only) Per No for D-73 Type [Top Slab - (3'5" x 1'4" x 3"), Supports - (6" x 1'1" x 1'10")].

DE

Jt. City Engineer (BRTS)
PCMC, Pimpri-18

Section AA'

Elevation 1

Plan

Fixing Detail

Elevation 2

Section BB'

TENDER DRAWING (DRAFT COPY)

PCMC Street Development Akurdi - Pimple Nilakh Pimpri Chinchwad Municipal Corporation	S1 - Pimple Nilakh, S2, S3, S4, and S5 - Akurdi			Consulting Team PAVETECH CONSULTANTS Project Management Consultants PRASANNA DESAI architecture, interior & urban design consultants	Dealt by : Nikhil Deorey	Date - 17/01/2018	
	Rev. No.	Date	Revised By	Description	Rectangular Seating With Hand Rest	Job No: D 73 200, 202	48 / 53
	00	00					
	00	00					