Pimpri Chinchwad Municipal Corporation

Name of the Work: Providing and Laying Pebble Beach Grass Paver Block.

Date:- 7/8/18

Rate analysis

Item: Providing and Laying brown / Grey coloured Cement Concrete Pebble Beach Grass Paver Block of size 500 x 330 x 80mm thick and of M-40 grade for Pebble Grass Surface Finish, laid in required pattern over 70mm thick compacted bed of Garden Soil for grass, Compacting and proper embedding / laying of each pebble paver block to be fixed into the Garden Soil bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand, finishing and sweeping extra sand etc complete as per direction of Engineer-in-Charge including transportation, loading, unloading and all other taxes and excluding GST.

Lowest rate from comparative, hence rate proposed is

Rs 1537.85 (Rs. One Thousand Five Hundred Thirty-Seven and Eighty-Fivepaise only) Per Sq.m. for Grey Colour.

Rs 1698.85 (Rs. One Thousand Six Hundred Ninty-Eight and Eighty-Five Paise only) Per Sq.m. for Brown Colour.

Jr. Engineer (BRTS)
PCMC, Pimpri-18

Dy. Engineer (BRTS)
PCMC, Pimpri-18

Executive Engineer (BRTS)
PCMC, Pimpri-18

Rate is approved as

Rs 1537.85 (Rs. One Thousand Five Hundred Thirty-Seven and Eighty-Five Paise only) Per Sq.m. for Grey Colour.

Rs 1698.85 (Rs. One Thousand Six Hundred Ninty-Eight and Eighty-Five Paise only) Per Sq.m. for Brown Colour.

Jt. City Engineer (BRTS)
PCMC, Pimpri-18