Pimpri Chinchwad Municipal Corporation

Name of the Work: Providing & fixing of Tactile Tiles.

Rate analysis

Date :- 7/8/18

Item: Providing & fixing of Tactile Tiles for footpath of size 300 x 300mm and 60mm thick of approved colour with top grooving of 260mm(L) x 35mm(w) x 5mm thick by leaving 20mm cover distance from corner edge and at 75mm centre for Directional Tactile tile and top grooving of 25mm dia. 5mm thickness placed at 50mm centre to centre distance by leaving 20mm cover distance all four sides for warner Tactile tile. Having high strength and high wear resistant cement concrete Tactile Tiles. The Tactile Tiles must confirm to IS 13801:1993. Laying Tiles in position over prepared bed of natural sand / crushed sand of 50 mm.
Tiles must be manufactured on automatic machines with mechanical vibration and rubberized moulds. The Tiles will be made using wear resistant material in the face mix as specified by the architects. Tiles must be cured in controlled environment to ensure efflorescence free material. Colour as specified by architect, using UV resistant colour pigments from laxness. as per detailed drawings & specifications and as directed by Engineer in charge for road works only. Including transportation, Loading, unloading and all other taxes and excluding GST.

Lowest rate from comparative, hence rate proposed is Rs 700 (Rs. Seven hundred Only) Per Sq.m

Jr. Engineer (BRTS)
PCMC, Pimpri-18

Dy. Engineer (BRTS)
PCMC, Pimpri-18

Executive. Engineer (BRTS)
PCMC, Pimpri-18

Rate is Approved as Rs 700 (Rs. Seven hundred Only) Per Sq.m

Jt. City Engineer (BRTS)
PCMC, Pimpri-18

SECTION dd'

Section ee'

Detail of Precast 'Directional' Tactile Concrete Paver

NOTE:
All Tactile and directional tiles will be of yellow pigmentation

SECTION cc'

Detail of Precast 'Warner' Tactile Concrete Paver

Detail Y (Scale 1:2)

PCMC Street Development Akurdi - Pimple Nilakh Pilot Pimpri Chinchwad Municipal Corporation	S1 - Pimple Nilakh, S2, S3, S4, and S5 - Akurdi			Consulting Team	TENDER DRAWING (DRAFT COPY)
	Rev. No. / Date / Revised By / Description			PAVETECH CONSULTANTS Project Management Consultants 5th floor, City square building, Shivaji nagar, Pune-411005	PRASANNA DESAI architecture, interior & urban design consultants 13, pranit apts, baner road, aundh, pune - 411 007 ph. +91 20 2565 1631 email: pdapune@rediffmail.com reg no. - ca / 82 / 6826
	00 / 00				Dealt by : Ankita Anand — Date - 17/01/2018
	00 / 00				Tactile Paving Detail — Job No. D 19 — 200, 202 / 16 / 53

Detail 1
Tactile Layout At Pedestrian Crossing

Detail 2
Tactile Turning Layout

TENDER DRAWING (DRAFT COPY)

PCMC Street Development Akurdi - Pimple Nilakh Pilot Pimpri Chinchwad Municipal Corporation	S1 - Pimple Nilakh, S2, S3, S4, and S5 - Akurdi			Consulting Team PAVETECH CONSULTANTS Project Management Consultants PRASANNA DESAI Architecture, interior & urban design consultants	Dealt by : Ankita Anand Date : 17/01/2018 Tactile Pattern Job No: D 20 200 17 202 53
	Rev. No.	Date	Revised By	Description	
	00	00			
	00	00			

D202D-1

D502D-1

D503B-1

D603E-1

D202D-2

FOTO
CERAMICA

lebration Cakes
HALAL CHICKEN
AWARMA & KEBAB
Coca-Cola
P