Pimpri Chinchwad Municipal Corporation

Name of the Work: Imprinting system for Stamped Concrete. Date:- 7/8/18

Rate analysis

Item: Applying and finishing the top surface of concrete, in accordance with sprinkling of Bomanite Colour Hardener at the rate of 0.27 kg. / Sq.ft., floating the surface with different types of floaters, application of Bomanite Release agent at the rate of 0.0113 kg/Sq.ft stamping the concrete with stamping tools, cleaning the surface with water and application of Acrylic based Sealer (Bomaseal) for finishing. Complete of stamped concrete overlays over M-20 concrete of 150mm thick-surface, interior, applied smooth, textured or stamped in various patterns and designs using stamps and semless texture skins. (excluding the cost of M-20 concrete of 150mm thickness) Spec. No.: As directed by Engineer in-charge including transportation,Loading,unloading and including all other taxes and excluding GST.

Lowest rate from comparative, hence rate proposed is Rs 538 (Rs. Five Hundred Thirty Eight Only)Per Sq.m.

Jr. Engineer (BRTS)	Dy. Engineer (BRTS)	Executive. Engineer (BRTS)
PCMC, Pimpri-18	PCMC, Pimpri-18	PCMC, Pimpri-18

Rate is Approved as Rs. 538 (Five Hundred Thirty Eight Rs. Only) Per Sq.m.

Jt. City Engineer (BRTS)

PCMC, Pimpri-18

Note:

1. **Footpath pattern** :- Ashlar Slate
   Color :- French Gray Shade
   BC-1 CH-00101-60

Stamped Concrete Footpath Detail

Sectional View of Stamped Concrete

TENDER DRAWING (DRAFT COPY)

PCMC Street Development
Akurdi - Pimple Nilakh Pilot
Pimpri Chinchwad Municipal Corporation

S1 - Pimple Nilakh, S2, S3, S4, and S5 - Akurdi

Rev. No.	Date	Revised By	Description
00	00		
00	00		

Consulting Team
PAVETECH CONSULTANTS
PRASANNA DESAI

Dealt by : Ankita Anand
Date - 17/09/2019

Stamp Concrete Details

Dwg. No. D 22
200, 202 19
53