Pimpri Chinchwad Municipal Corporation

Name of the Work: Providing and laying Grass Paver Block.

Date:- 7/8/18

Rate analysis

Item: Providing and laying factory made Cement concrete Grass paver blocks of size 600mm x 400mm x 60mm thickness of M-35 grade chamfered at all edges to maintain web thickness of 47 mm including 8 square shaped through openings placed diagonally of 94mm x 94mm with 2 triangular openings of 94mm x 94 mm on the longer side and 1 triangular opening of 94mm x 94mm on shorter side of CC grass paver block to match the opening of other paver block to develop the overall pattern as detailed in drawing, made by table vibratory method using PU mould, laid in of grey colour & required pattern over 50mm thick compacted bed of garden soil, compacting and proper embedding / laying of paver blocks into the soil layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand/soil etc. complete including transportation, loading, unloading, all other taxes and excluding GST.

Lowest rate from comparative, hence rate proposed is Rs .1237.40 (Rs. One Thousand Two Hundred Thirty Seven and Forty Paise only) Per Sq.m.

Jr. Engineer (BRTS)
PCMC, Pimpri-18

Dy. Engineer (BRTS)
PCMC, Pimpri-18

Executive. Engineer (BRTS)
PCMC, Pimpri-18

Rate is Approved as Rs .1237.40 (Rs. One Thousand Two Hundred Thirty Seven and Forty Paise only) Per Sq.m.

DE

Jt. City Engineer (BRTS)
PCMC, Pimpri-18

Individual Exposed Stone Pebble Plan
(80 mm Thick Gray in Colour)
(as per specification)

Earth Filling for the grass to grow

Grass Pavers
80 mm Thick Grey in Colour
(as per specification)

DETAIL XX' (Scale 1:5)

PCMC Street Development Akurdi - Pimple Nilakh Pilot Pimpri Chinchwad Municipal Corporation	S1 - Pimple Nilakh, S2, S3, S4, and S5 - Akurdi	Consulting Team PAVETECH CONSULTANTS Project Management Consultants PRASANNA DESAI architecture, interior & urban design consultants	Dealt by : Nikhil Deorey	Date : 29 / 05 / 2018	TENDER DRAWING (DRAFT COPY)
	Rev. No. / Date / Revised By / Description		Grass Pavers	Job No. 200, 202	D 78 / 52 / 53