Pimpri Chinchwad Municipal Corporation

Name of the Work: Providing and Fixing Camel Brown Sand Stone Seat out.

Date :- 7/8/2018

Rate Analysis

Item: Providing and Fixing Camel Brown Sand Stone **bench of Type D-73, [(01 Top Slab - (3'5" x 1'4" x 3")** **and 02 Supports - (6" x 1'1" x 1'10")]** with top surface polished and remaining surfaces natural finish, fixed with cladex chemical as per Detailed Drawing Attached and Type suggested by Architect and as directed by Engineer In charge including transportation, loading, unloading and all other taxes and excluding GST.

Lowest rate from comparative, hence rate proposed is Rs. 16000 (Rs. Sixteen Thousand only) Per No for D-73 Type [Top Slab - (3'5" x 1'4" x 3"), Supports - (6" x 1'1" x 1'10")].

Jr. Engineer (BRTS)
PCMC, Pimpri-18

Dy. Engineer (BRTS)
PCMC, Pimpri-18

Executive. Engineer (BRTS)
PCMC, Pimpri-18

Rate is Approved as Rs. 16000 (Rs. Sixteen Thousand Only) Per No for D-73 Type [Top Slab - (3'5" x 1'4" x 3"), Supports - (6" x 1'1" x 1'10")].

Jt. City Engineer (BRTS)
PCMC, Pimpri-18

OE

Section AA'

Elevation 1

Plan

Fixing Detail

Elevation 2

Section BB'

TENDER DRAWING (DRAFT COPY)

Dealt by : Nikhil Deorey	Date - 17/01/2018
Rectangular Seating With Hand Rest	Job No: D 73 200, 48

Consulting Team

PAVETECH CONSULTANTS
Project Management Consultants

PRASANNA DESAI
Architecture, Interior & Urban design consultants
13 prandi apts, baner road, aundh, pune - 411 007 ph. - +91 20 2565 1931

treet Development
- Pimple Nilakh
nchwad Municipal Corporation

S1 - Pimple Nilakh, S2, S3, S4, and S5 - Akurdi

Rev. No.	Date	Revised By	Description
00	00		