

Pimpri Chinchwad Municipal Corporation Pimpri 18.

RATE ANALYSIS

Removing & Refixing Kerb Stone

Rate From SSR 2017-18

Item :- Removing & refixing RCC precast kerb stone of all size embeded in CC 1:2:4 with required all necessary excavation & transporting the excavated material pointing the exposed faces with CM 1:2 curing etc.complete.As directed by Engineer in charge.

Unit 10 Rmt

Sr.No.	Description	Quantity	Rate	Unit	Amount	Remark
1)	Removing of all old R.C.C.Kerb stone & lean concrete	0.7	317.1	Cum	221.97	
2)	Labour for Cleaning R.C.C.Kerb					
	a.Mazdoor (M) 1 X 0.25	0.25	448.00	Day	112.00	
	b.Mazdoor (F)1 X 0.25	0.25	448.00	Day	112.00	
3)	Labour for dressing excavated pits					
	a.Mazdoor (M)1 X 0.25	0.25	448.00	Day	112.00	
	b.Mazdoor (F)1 X 0.25	0.25	448.00	Day	112.00	
4)	Labour for Refixing R.C.C Kerb Stone					
	a.Mason 2nd Class 1x0.25	0.25	494.00	Day	123.50	
	b.Mazdoor (M) 2x0.25	1	448.00	Day	448.00	
	c.Mazdoor (F) 1x0.25	0.25	448.00	Day	112.00	
	Total Labour A				1353.47	
5)	Conctere					
	C.C.1:2:4	0.7	4394.54	Cum	3076.18	
	Flush pointing of kerb stone for expose face	9	121.59	sqm	1094.31	
	Total B				4170.49	
	Total of (A+B)=C				5523.96	
6)	Other than labour & machinery					
	a)Transportation of R.C.C Kerb Stone				0.00	
	b)Transportation of Grit (Within PCMC limit For 10 KM)	0	0.00	Cum	0.00	
	c)Transportation of concrete (For 3 KM)	0	0.00	Cum	0.00	
	Total D				0.00	
	Total (C+D) = E				5523.96	
7)	Add over head Charges @ 10% on ©				552.40	
	Add 5% For PCMC limit on (E)				276.20	
	Total Rs.				6352.55	
	Rate for 10 Rmt there for 1 Rmt				6353.00	
	Say Rs.				63.53	

Rate Proposed For the item is Rs. 63.53 Per Rmt

**Junior Engineer
Civil "B" ward**

**Deputy Engineer
Civil "B" ward**

**Executive Engineer
Civil "B" ward**

Rate Approved For Rs. 63.53 Rupess Sixty Three and Fifty Three Paise Only

without GST.

**City Engineer
PCMC**