## Pimpri Chinchwad Municipal Corporation, Pimpri, Pune - 18.

## Rate Analysis

Date - 29/5/18

Name of Work - Various works at Pimpri Chinchwad Municipal Corporation Area.

Item - Designing, providing fabrication, supplying & fixing in position structural glazing to external face of the building straight in plan consisting of main panel work of vertical & horizontal made out of specially designed extruded sss38 x 83mm powder coated alluminium section, anchor to RCC element through adequately designed powder coated MS clamps, bracket using 5mm thick one way reflective make Saint Gobain Glass (Blue/Bronze/Green Reflective Glass) & weather silicon sealant of approved grade (Direct Sticking) Material used Mullion Section: 63 x 83mm Transform Section: 63mm x 38mm Spacer tape, Silidon sealant SSG 4000 ULTRA GLAZED /995 Dow Coring, Silprooof / 789, Glass equivalent 5.00mm thick one way reflective in Blue Colour (Saint Gobain) The joints shall be properly sealed with approved silicon sealant to make the joints watertight and weather proof including fixing over alluminium frame using mechanical fastenrs such as alluminium cleats and fasteners, specially designed frame work with vertical and horizontal members of extruded alluminium section which shall be made of alloy 6063 T6, as approved by the Engineer in charge (as per drawing enclosed) The work shall be complete as per specification and direction of Engineer in charge including all other taxes excluding GST .etc complete

Lowest rate from comparative statement is Rs.4820/-(Four Thousand Eight Hundred Twenty only)Per

Hence proposed rate is Rs.4820/-(Four Thousand Eight Hundred Twenty only)Per Sqmt.

A Zone PCMC

Deputy Engineer

A Zone PCMC

Executive Engineer

A Zone PCMC

Rate is approved Rs.4820/-(Four Thousand Eight Hundred Twenty only)Per Sqmt.

g. Mrc DE

City Engineer

PCMC, Pimpri - 18