

Pimpri Chinchwad Municipal Corporation, Pimpri-18.

Providing and fixing Precast tapering R. C. C. M-40 grade Kerb type-VI-A

Rate from SSR-2017-18

Date:- 3-7-18

without receipts

Providing and Fixing Precast tapering R.C.C. M-40 grade Kerb Type-VI-A (as per detailed drawing attached), in R-40 IRC specification (1000 x 250-150X350) embedded 200 mm below Ground neatly with fixing in Position Cement Mortar 1:2 etc complete, including redoing the surface as specified and directed by Engineer-In-Charge including transportation, Loading, unloading and including all other taxes and excluding GST.

Description	No.	L	B	D	Qty.	Rate	Unit	Amt.	Remark
For 100 Nos									
A] For RCC M-40 without SCADA for Footing									
Bottom Portion (Below RTL)	100	1.0	0.25	0.10	2.50				
Top Portion (Above RTL)	100	1.0	0.15	0.25	3.75				
					Total A	6.250	5535.500	Cum	34596.88
									25.19, BDF 3/298
									34596.88
B] Steel Reinforcement									
8mm	6	100			600		Rmt.	600.00	
							Kg / Rmt.	0.396	
							Total (i)	Kg.	237.60
8mm Vertical Bars	335	0.91			304.85		Rmt.	304.85	
							Kg / Rmt.	0.396	
							Total (ii)	Kg.	120.72
									Gross Total (i+ii)
							Total B	48.624	Rs.
									17423.14
									26.33, BDF 17/306
C] Labour Charges for fixing in position									
100 Rmt will be fixed in a day by 3 skilled & 3 unskilled labours									
Mason IInd class	3	Nos				494.00	per day	1482.00	PCMC Rate List
Mazdoor unskilled (Heavy male)	3	Nos				448.00	per day	1344.00	PCMC Rate List
						Total C		Rs.	2826.00
D] Transportation, Loading & Unloading									
Considering Transportation by Truck 10 MT Capacity (50 Rmt will be transported in one trip)									
truck transport rent trip (2 trip)		2			2	631.480	Per/Trip	1262.96	SSR C-Statement
							Total	1262.96	
									56108.98
							Total Rate for 100 No	A+B+C+D	56108.98
							Therefore Rate Per No	Total Rs.	561.09
							Say Rs.	561.09	Per No
							Therefore Rate per Rmt = One No in One Rmt	Say Rs.	561.09
									Per Rmt

Rate is Proposed for Kerb Type-VI-A (250X150X350) in RCC M-40 without SCADA Rs. 561.09 Per Rmt

Rate In Words :- Rs. Five Hundred Sixty One and Nine Paise only



PaveTech Consultants
Pune

[Signature]
Junior Engineer
PCMC

[Signature]
Deputy Engineer
PCMC

[Signature]
Executive Engineer
PCMC

08/74

Rate is Approved for Kerb Type-VI-A (250X150X350) in RCC M-40 without SCADA Rs. 561.09 Per Rmt

Rate In Words :- Rs. Five Hundred Sixty One and Nine Paise only

26/
[Signature]
DE

[Signature]
Joint City Engineer
PCMC

