

## RATE ANALYSIS

<b>ITEM</b>	Providing & laying RCC half round pipe I.S. NP-2 Class of <b>250mm</b> diameter on proper line, level & slope including pointing in C.M. 1:2 and curing complete etc. directed by the Engineer Incharge Complete.
-------------	---

250mm  
10 Rmt  
Per Rmt

Sr.	Description	Quantity	Rate Rs.	Units	Amount Rs.	Remark
1	<u>Labour</u>					NIL
	Mason II Class Skilled	1/8	494.00	No./Day	61.75	
	Unskilled Heavy Male Mazdoor	1/8	448.00	No./Day	56.00	
				<b>Total Rs.</b>	<b>117.75</b>	
Sr.	Description	Quantity	Rate Rs.	Units	Amount Rs.	Remark
2	<u>Material</u>					NIL
	Pipe with all taxes	10	150	Rmt	1500.00	
	Jounting & pointing	Lumpsum			10.00	
				<b>Total Rs.</b>	<b>1510.00</b>	
Sr.	Description	Quantity	Rate Rs.	Units	Amount Rs.	Remark
3	<u>Other than Labour &amp; Materials</u>	0	0	0	0	NIL
		0	0	<b>Total Rs.</b>	<b>0</b>	
<b>Total of 1 to 3</b>					<b>1627.75</b>	
4	<u>sundries @ 1/2%</u>			Rs.	8.13	
				<b>Total Rs.</b>	<b>1635.88</b>	
5	<u>Watercharge @1%</u>			Rs.	16.35	
				<b>Total Rs.</b>	<b>1652.23</b>	
6	<u>Add for over head charges@ 10 %</u>			Rs.	165.22	
				<b>Total Rs.</b>	<b>1817.45</b>	Per 10 Rmt

**JOINT CITY ENGINEER**  
P.C.M.C., Pimpri 18