

PIMPRI CHINCHWAD MUNICIPAL CORPORATION

RATE ANALYSIS

Date - 29/6/18

ITEM Providing & laying RCC half round pipe I.S. NP-2 Class of 150mm diameter on proper line, level & slope including pointing in C.M. 1:2 and curing complete etc. directed by the Engineer Incharge Complete.

Half Round Pipe Diameter 150mm
Unit Considered 10 Rmt
Mode of Measurement Per Rmt

Sr.	Description	Quantity	Rate Rs.	Units	Amount Rs.	Remark
1	Labour					
	Mason II Class Skilled	1/8	494.00	No./Day	61.75	NIL
	Unskilled Heavy Male Mazdoor	1/8	448.00	No./Day	56.00	
				Total Rs.	117.75	
Sr.	Description	Quantity	Rate Rs.	Units	Amount Rs.	Remark
2	Material					
	Pipe with all taxes	10	95	Rmt	950.00	NIL
	Jounting & pointing	Lumpsum			10.00	
				Total Rs.	960.00	
Sr.	Description	Quantity	Rate Rs.	Units	Amount Rs.	Remark
3	Other than Labour & Materials	0	0	0	0	NIL
		0	0	Total Rs.	0	
Total of 1 to 3					1077.75	
4	sundries @ 1/2%			Total Rs.	5.38	
				Rs.	1083.13	
5	Watercharge @1%			Total Rs.	10.83	
				Total Rs.	1093.96	
6	Add for over head charges@ 10 %			Rs.	109.39	
				Total Rs.	1203.35	Per 10 Rmt

Rate is Proposed for Rs. 120.33 Per Rmt

3000 Kew
JUNIOR ENGINEER
SLUM ENGG. DEPT.
PCMC

Khondy
DEPUTY ENGINEER
SLUM ENGG. DEPT.
PCMC

Shrawan
EXECUTIVE ENGINEER
SLUM ENGG. DEPT.
PCMC

Om
JUNIOR ENGINEER
T.S. Department
P.C.M.C., Pimpri 18

the
DEPUTY ENGINEER
T.S. Department
P.C.M.C., Pimpri 18

Pankaj
EXECUTIVE ENGINEER
T.S. Department
P.C.M.C., Pimpri 18

Rate is approved as Rs. 120.33/- per Rmt

S
JOINT CITY ENGINEER
P.C.M.C., Pimpri 18

*dy
the
DE*