

PIMPRI CHINCHWAD MUNICIPAL CORPORATION

RATE ANALYSIS

ITEM Providing & laying RCC half round pipe I.S. NP-2 Class of **300mm** diameter on proper line, level & slope including pointing in C.M. 1:2 and curing complete etc. directed by the Engineer Incharge Complete.

Half Round Pipe Diameter

300mm

Unit Considered


10 Rmt


Mode of Measurement


Per Rmt


Sr.	Description	Quantity	Rate Rs.	Units	Amount Rs.	Remark
1	Labour					
	Mason II Class Skilled	1/8	494.00	No./Day	61.75	NIL
	Unskilled Heavy Male Mazdoor	1/8	448.00	No./Day	56.00	
				Total Rs.	117.75	
Sr.	Description	Quantity	Rate Rs.	Units	Amount Rs.	Remark
2	Material					
	Pipe with all taxes	10	250	Rmt	2500.00	NIL
	Jounting & pointing	Lumpsum			10.00	
				Total Rs.	2510.00	
Sr.	Description	Quantity	Rate Rs.	Units	Amount Rs.	Remark
3	Other than Labour & Materials	0	0	0	0	NIL
		0	0	Total Rs.	0	
Total of 1 to 3					2627.75	
4	sundries @ 1/2%			Rs.	13.13	
				Total Rs.	2640.88	
5	Watercharge @1%			Rs.	26.40	
				Total Rs.	2667.28	
6	Add for over head charges@ 10 %			Rs.	266.72	
				Total Rs.	2934.00	Per 10 Rmt


Rate is Proposed for Rs. 293.40 Per Rmt



JUNIOR ENGINEER
SLUM ENGG. DEPT.
PCMC


DEPUTY ENGINEER
SLUM ENGG. DEPT.
PCMC


EXECUTIVE ENGINEER
SLUM ENGG. DEPT.
PCMC



JUNIOR ENGINEER
T.S. Department
.P.C.M.C., Pimpri 18


DEPUTY ENGINEER
T.S. Department
P.C.M.C., Pimpri 18


EXECUTIVE ENGINEER
T.S. Department
P.C.M.C., Pimpri 18

Rate is approved as Rs. 293.40/Per Rmt


JOINT CITY ENGINEER
P.C.M.C., Pimpri 18


JOINT CITY ENGINEER
P.C.M.C., Pimpri 18