PIMPRI CHINCHWAD MUNICIPAL CORPORATION **RATE ANALYSIS**

Providing & laying RCC half round pipe I.S. NP-2 Class of 450mm diameter on proper line, level & slope including pointing in C.M. 1:2 and curing complete etc. directed by the Engineer Inchargre Complete.

Half Round Pipe Diameter 450 mm 10 Rmt Unit Considered Mode of Measurement Per Rmt

+		T a	5 . 5	1		D .
Sr.	Description	Quantity	Rate Rs.	Units	Amount Rs.	Remark
1	Labour					
	Mason II Class Skilled	1/8	494.00	No./Day	61.75	NIL
	Unskilled Heavy Male Mazdoor	1/8	448.00	No./Day	56.00	
				Total Rs.	117.75	
Sr.	Description	Quantity	Rate Rs.	Units	Amount Rs.	Remark
2	Material Material					
	Pipe with all taxes	10	550	Rmt	5500.00	NIL
	Jounting & pointing	Lumpsum			10.00	
				Total Rs.	5510.00	
Sr.	Description	Quantity	Rate Rs.	Units	Amount Rs.	Remark
3	Other than Labour & Materials	0	0	0	0	NIL
		0	0	Total Rs.	0	
		<u> </u>	Tot	tal of 1 to 3	5627.75	
4	sundries @ 1/2%			Total Rs.	28.13	
				Rs.	5655.88	
5	Watercharge @1%			Total Rs.	56.55	
			6	Total Rs.	5712.43	
6	Add for over head charges@ 10 %			Rs.	571.24	
				Total Rs.	6202 67	Per 10 Rm

Rate is Proposed for Rs. 628.36 Per Rmt

JUNIOR ENGINEER SLUM ENGG. DEPT.

PCMC

SLUM ENGG. DEPT.

PCMC

EXECUTIVE ENGINEER

SLUM INGG. DEPT.

PCMC

JUNIOR ENGINEER

T.S. Deparment

.P.C.M.C., Pimpri 18

DEPUTY ENGINEER

T.S. Deparment

P.C.M.C., Pimpri 18

EXECUTIVE ENGINEER

T.S. Deparment

P.C.M.C., Pimpri 18

Rate (5 approved as B. 628.36 - Port

JOINT CITY ENGINEER P.C.M.C., Pimpri 18